

## **CALCO CONCRETE PUMPING INC.**

Operation Manager Calco Concrete Pumping

Gypsum Branch

Eric Isenhardt

### **Steps "123"**

#### **PUMP TRUCK BASICS**

Pretrip Truck

Make sure transmission is in neutral

Depress clutch fully

Start Truck

Let it warm up

Place Transmission in appropriate gear

Apply foot brake

Choose next appropriate gears

Arrive at jobsite

Set parking brake

Get out of truck and check jobsite.

Set pump up so it is within 3 degrees of level and make sure you have a safe entrance and exit for mixers

Put transmission in 7<sup>th</sup> gear and pull the PTO

Go to back panel and clear out panel.

Hit horn switch to clear out

Press outrigger switch and activate levers for outriggers.

Put pat under outrigger

Apply outrigger pressure to all outriggers.

Grab remote box and put n remote mode.

Unfold boom into a "A" frame position to prime.

Put prime in hopper and strke forward 4 times.

Put concrete in hopper and turn on pump until good concrete comes out.

Complete pour.

Fill hopper with water and push out concrete.

Fold up boom

Put remote in Cab

Go back and put in local mode.

Stow outriggers and put pads in rack.

Wash out hopper.

Proceed back to yard.

Do Postrip.